

GPS #: **2177**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/D-1

City / Location: Unin., Orange County

Scale Factor: 0.99996929

Ellipsoid Red. Factor: 0.99988003

Combination Factor: 0.99984932

Convergence Angle: -00 38 35.43223

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 59.55754	117 25 13.57266	2182092.578	6205477.894	2507.380
2007.00	33 38 59.57473	117 25 13.58820	2182094.33	6205476.60	

References: RSB 160/17-32

Description:

FD 1" IP WITH 1 3/8" OCS BRASS TAG STAMPED "GPS 2177 9-96" UP 0.1' IN DIRT. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY AND N'LY 23.6 MILES ALONG ORTEGA HWY. TURN LEFT, N'LY, ON MONTE VISTA, PROCEED 0.4 MILES TO A WROUGHT IRON FENCE CONTINUE ALONG 330' TO A THREE WAY INTER CONTINUE ALONG ON THE CENTER RD. 100' TURN RIGHT, NE'LY, 130' TO THE MONUMENT.

