

GPS #: **2178**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/D-1

City / Location: Unin., Orange County

Scale Factor: 0.99996918

Ellipsoid Red. Factor: 0.99988093

Combination Factor: 0.99985011

Convergence Angle: -00 38 36.92301

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 55.30748	117 25 16.28554	2181665.586	6205243.748	2488.528
2007.00	33 38 55.32458	117 25 16.30113	2181667.33	6205242.45	

References: RSB 160/17-32

Description:

FD 1" IP WITH PLASTIC CAP AND 3/4" BRASS TAG STAMPED "LS 3832" FLUSH IN A.C. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY AND N'LY 23.6 MILES ALONG ORTEGA HWY. TURN LEFT, N'LY, ON MONTE VISTA, PROCEED 0.4 MILES TO THE MONUMENT AT APPROXIMATE CENTER OF THE RD. 17' E'LY OF A WROUGHT IRON GATE.

