

GPS #: **2179**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99996830

Ellipsoid Red. Factor: 0.99988685

Combination Factor: 0.99985515

Convergence Angle: -00 38 53.35928

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 21.49191	117 25 46.19590	2178276.254	6202676.723	2364.779
2007.00	33 38 21.50913	117 25 46.21155	2178278.01	6202675.42	

References: RSB 160/17-32

Description:

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "S20 SE NW NW 1/256 LS 5242 1986 UNLAWFUL TO DISTURB, CADASTRAL SURVEY". LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD. (LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.5 MILES, MONUMENT IS ON N'LY SHOULDER OF RD.

