

GPS #: **2180**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/C-3

City / Location: Unin., Orange County

Scale Factor: 0.99996817

Ellipsoid Red. Factor: 0.99988837

Combination Factor: 0.99985654

Convergence Angle: -00 38 53.35725

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 16.53889	117 25 46.19221	2177775.635	6202671.372	2333.089
2007.00	33 38 16.55610	117 25 46.20784	2177777.39	6202670.07	

References: RSB 160/17-32

Description:

FD 3/4" X 24" DR. ROD WITH 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "ORANGE CO RIV. CO RLS 5242 1986 UNLAWFUL TO DISTURB, CADASTRAL SURVEY" FLUSH IN DIRT. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.4 MILES, TURN LEFT, S'LY, PARK. HIKE S'LY 500' TO FOREST BOUNDARY.

