

GPS #: **2181**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/C-3

City / Location: Unin., Orange County

Scale Factor: 0.99996786

Ellipsoid Red. Factor: 0.99988805

Combination Factor: 0.99985591

Convergence Angle: -00 38 53.35224

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 04.56744	117 25 46.18310	2176565.641	6202658.454	2339.746
2007.00	33 38 04.58460	117 25 46.19875	2176567.39	6202657.15	

References: RSB 160/17-32

Description:

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED " UNLAWFUL TO DISTURB, CADASTRAL SURVEY", UP 1.0'. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.7 MILES, TURN LEFT, S'LY, 30' (NOW DIRT) TO GATE (PRVT LOCK PH# 714-493-7634, MR. SANCHEZ) CONTINUE ALONG 200' ON FAINT TRAIL, TO THE MOST N'LY GATE OF A FENCED YARD (PRVT LOCK) CONTINUE ALONG SW'LY TO A GATE ON THE SOUTH SIDE OF SAID YARD. CONTINUE ALONG, S'LY, UPHILL 0.4 MILES TO A JUNCTION THENCE ALONG E'LY 0.5 MILES TO JUNCTION CONTINUE 100' PARK AT THE BEND WHERE THE RD. HEADS WEST. HIKE 450' N'LY ALONG FOREST BOUNDARY LINE TO THE MONUMENT.

