

GPS #: **2182**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/B-3

City / Location: Unin., Orange County

Scale Factor: 0.99996787

Ellipsoid Red. Factor: 0.99988404

Combination Factor: 0.99985191

Convergence Angle: -00 38 59.95242

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 04.95460	117 25 58.19395	2176616.276	6201643.442	2423.545
2007.00	33 38 04.97180	117 25 58.20959	2176618.03	6201642.14	

References: RSB 160/17-32

Description:

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "T6S R5W 1/14 S19 S20 RLS 5242 1986 UNLAWFUL TO DISTURB, CADASTRAL SURVEY", UP 0.3'. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.7 MILES, TURN LEFT, S'LY, 30' (NOW DIRT) TO GATE (PRVT LOCK PH# 714- 493-7634, MR. SANCHEZ) CONTINUE ALONG 200' ON FAINT TRAIL, TO THE MOST N'LY GATE OF A FENCED YARD (PRVT LOCK) CONTINUE ALONG SW'LY TO A GATE ON THE SOUTH SIDE OF SAID YARD. CONTINUE ALONG, S'LY, UPHILL 0.4 MILES TO A JUNCTION HIKE ALONG RD. 100', E'LY, THENCE S'LY INTO ROCKS.

