

GPS #: **2183**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/B-4

City / Location: Unin., Orange County

Scale Factor: 0.99996754

Ellipsoid Red. Factor: 0.99989217

Combination Factor: 0.99985971

Convergence Angle: -00 38 59.86161

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 51.71349	117 25 58.02870	2175277.805	6201642.231	2253.585
2007.00	33 37 51.73070	117 25 58.04444	2175279.56	6201640.92	

References: RSB 160/17-32

Description:

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "S1/16 S20 RM R.L.S. 5242 1986 UNLAWFUL TO DISTURB, CADASTRAL SURVEY", UP 0.3' FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.7 MILES, TURN LEFT, S'LY, 30' (NOW DIRT) TO GATE (PRVT LOCK PH# 714- 493-7634, MR. SANCHEZ) CONTINUE ALONG 200' ON FAINT TRAIL, TO THE MOST N'LY GATE OF A FENCED YARD (PRVT LOCK) CONTINUE ALONG SW'LY TO A GATE ON THE SOUTH SIDE OF SAID YARD. CONTINUE ALONG, S'LY, UPHILL 0.4 MILES TO A JUNCTION THENCE E'LY 0.1 MILES TO A LARGE OUTCROPPING OF ROCK. HIKE S'LY 200' BY SAID OUT CROPPING, PASSING ON THE E'LY SIDE OF ROCKS, CONTINUE 500' S'LY ALONG RIDGE TOP TO THE N'LY LINE OF S 1/2 SE 1/4 SEC. 19 (INDICATED BY FOREST BNDY PADDLES) MONUMENT IS 20' W'LY OF RIDGETOP.

