

**GPS #:** **2184**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 895/B-4

City / Location: Unin., Orange County

Scale Factor: 0.99996755

Ellipsoid Red. Factor: 0.99989121

Combination Factor: 0.99985877

Convergence Angle: -00 39 03.87582

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 51.95723	117 26 05.33367	2175309.453	6201024.888	2273.617
2007.00	33 37 51.97446	117 26 05.34938	2175311.21	6201023.58	

References: RSB 160/17-32

**Description:**

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "RLS 5242 1986 CO LINE UNLAWFUL TO DISTURB, CADASTRAL SURVEY". LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY 0.7 MILES, TURN LEFT, S'LY, 30' (NOW DIRT) TO GATE (PRVT LOCK PH# 714-493-7634, MR. SANCHEZ) CONTINUE ALONG 200' ON FAINT TRAIL, TO THE MOST N'LY GATE OF A FENCED YARD (PRVT LOCK ) CONTINUE ALONG SW'LY TO A GATE ON THE SOUTH SIDE OF SAID YARD. CONTINUE ALONG, S'LY, UPHILL 0.4 MILES TO A JUNCTION THENCE SW'LY 0.3 MILES, PARK ON SOUTH SIDE BY ROCK OUTCROPING. HIKE S'LY 500' ALONG RIDGETOP TO INTER OF FOREST BOUNDARY AND COUNTY LINE.

