

GPS #: **2185**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 894/J-4

City / Location: Unin., Orange County

Scale Factor: 0.99996757

Ellipsoid Red. Factor: 0.99986645

Combination Factor: 0.99983403

Convergence Angle: -00 39 34.46611

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 52.93548	117 27 01.00120	2175462.162	6196319.441	2791.169
2007.00	33 37 52.95263	117 27 01.01683	2175463.91	6196318.14	

References: RSB 160/17-32

Description:

FD 3 1/4" ALUMINUM U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE DISK STAMPED "S 1/16 S19 LS 5242 1986 UNLAWFUL TO DISTURB, CADASTRAL SURVEY", FLUSH IN GRANITE ROCK. LOCATED FROM THE 5 FREEWAY AND ORTEGA HWY. PROCEED E'LY 22.6 MILES ON ORTEGA HWY. TURN LEFT ON LONG CANYON RD.(LOS PINOS/McCONVILLE EXIT) CONTINUE E'LY ABOUT 1.5 MILES TURN LEFT, S'LY, CONTINUE ALONG IN THE FORESTRY TRAILER HOUSING TO THE MOST S'LY END. HIKE UP A SMALL HILL, CONTINUE ON S'LY HIKING TRAIL. (TO A DIRT RD.) HIKE ON THE MOST W'LY DIRT RD. GOING S'LY 3800' FOLLOWING ALONG W'LY RD. THAT FOLLOWS NEAR THE. EAST LINE OF SEC. 19 TO S 1/16 CORNER, AT NOB HILL.

