

GPS #: 2503

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 801/E-7

City / Location: Unin., Orange County

Scale Factor: 0.99998277

Ellipsoid Red. Factor: 0.99996534

Combination Factor: 0.99994812

Convergence Angle: -00 48 23.98756

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 05.33215	117 43 04.61270	2226271.573	6115550.226	724.529
2007.00	33 46 05.34855	117 43 04.62881	2226273.25	6115548.89	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD HEX BAR WITH PUNCH, IN OCS WELL MONUMENT DOWN 1.2'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 3.4 MILES E'LY FROM ITS INTER WITH JAMBOREE RD., 0.1 MILE W'LY FROM THE IRVINE LAKE ENTRANCE. PER RSB 173/1-10.

