

GPS #: **2504**

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 801/E-7

City / Location: Unin., Orange County

Scale Factor: 0.99998267

Ellipsoid Red. Factor: 0.99996602

Combination Factor: 0.99994869

Convergence Angle: -00 48 21.03368

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 02.36017	117 42 59.23730	2225964.802	6115999.752	710.382
2007.00	33 46 02.37669	117 42 59.25324	2225966.49	6115998.43	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD HEX BAR WITH PUNCH, IN OCS WELL MONUMENT DOWN 1.0'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 3.5 MILES E'LY FROM ITS INTER WITH JAMBOREE RD., 100' +/- W'LY FROM THE IRVINE LAKE ENTRANCE. PER RSB 173/1-10.

