

GPS #: 2508

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 801/F-7

City / Location: Unin., Orange County

Scale Factor: 0.99998194

Ellipsoid Red. Factor: 0.99996544

Combination Factor: 0.99994737

Convergence Angle: -00 48 04.30655

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 42.29309	117 42 28.79762	2223900.529	6118540.901	722.623
2007.00	33 45 42.30954	117 42 28.81355	2223902.21	6118539.58	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD HEX BAR WITH PUNCH, IN OCS WELL MONUMENT DOWN 1.2'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 2.35 MILES W'LY FROM ITS INTER WITH SILVERADO CANYON RD. PER RSB 173/1-10.

