

GPS #: **2514**

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/G-1

City / Location: Unin., Orange County

Scale Factor: 0.99998125

Ellipsoid Red. Factor: 0.99996320

Combination Factor: 0.99994445

Convergence Angle: -00 47 42.17777

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 23.12023	117 41 48.52817	2221915.318	6121913.509	769.362
2007.00	33 45 23.13609	117 41 48.54465	2221916.94	6121912.14	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD HEX BAR WITH PUNCH, IN OCS WELL MONUMENT DOWN 1.2', LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.7 MILES W'LY FROM ITS INTER WITH SILVERADO CANYON RD. PER RSB 173/1-10.

