

GPS #: **2516**

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/J-2

City / Location: Unin., Orange County

Scale Factor: 0.99998058

Ellipsoid Red. Factor: 0.99995789

Combination Factor: 0.99993847

Convergence Angle: -00 47 11.17572

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 04.27022	117 40 52.11131	2219944.356	6126650.299	880.307
2007.00	33 45 04.28659	117 40 52.12721	2219946.03	6126648.98	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM OCS DISK STAMPED "EC 22 A.O. 87", IN AN OCS WELL, LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 0.6 MILES W'LY FROM ITS INTER WITH SILVERADO CANYON RD. PER RSB 173/1-10.

