

GPS #: **2528**

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/C-4

City / Location: Unin., Orange County

Scale Factor: 0.99997831

Ellipsoid Red. Factor: 0.99995165

Combination Factor: 0.99992996

Convergence Angle: -00 46 13.97998

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 58.44470	117 39 08.02775	2213171.776	6135348.534	1010.825
2007.00	33 43 58.46128	117 39 08.04347	2213173.47	6135347.23	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR EC 6-1974", IN OCS WELL MONUMENT DOWN 1.7'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.7 MILES E'LY FROM ITS INTER WITH SILVERADO CANYON RD. PER RSB 173/1-10.

