

GPS #: 2533

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/D-5

City / Location: Unin., Orange County

Scale Factor: 0.99997777

Ellipsoid Red. Factor: 0.99995119

Combination Factor: 0.99992896

Convergence Angle: -00 46 10.11893

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 42.18050	117 39 01.00151	2211519.938	6135919.804	1020.398
2007.00	33 43 42.19676	117 39 01.01840	2211521.60	6135918.40	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR PI 14 6-1974", IN OCS WELL MONUMENT DOWN 1.7'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 2.0 MILES E'LY FROM ITS INTER WITH SILVERADO CANYON RD., 300' +/- W'LY FROM ITS INTER WITH JACKSON RANCH RD. NORTH. PER RSB 173/1-10.

