

GPS #: 2536

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/D-5

City / Location: Unin., Orange County

Scale Factor: 0.99997724

Ellipsoid Red. Factor: 0.99995021

Combination Factor: 0.99992744

Convergence Angle: -00 46 06.57878

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 26.14756	117 38 54.55923	2209892.147	6136442.129	1041.035
2007.00	33 43 26.16414	117 38 54.57500	2209893.84	6136440.82	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR PI 17 1974", IN OCS WELL MONUMENT DOWN 2.0'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 2.35 MILES E'LY FROM ITS INTER WITH SILVERADO CANYON RD. PER RSB 173/1-10.

