

GPS #: 2551

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997466

Ellipsoid Red. Factor: 0.99993875

Combination Factor: 0.99991341

Convergence Angle: -00 45 52.24270

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 05.63862	117 38 28.47073	2201725.458	6138536.878	1280.526
2007.00	33 42 05.65529	117 38 28.48637	2201727.16	6138535.58	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR BC 6-1974", IN OCS WELL MONUMENT DOWN 1.7'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.9 MILES NW'LY FROM ITS INTER WITH LIVE OAK CANYON RD., 200' +/- NW'LY FROM FALCON RD. PER RSB 173/1-10.

