

GPS #: 2554

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/F-2

City / Location: Unin., Orange County

Scale Factor: 0.99997430

Ellipsoid Red. Factor: 0.99993757

Combination Factor: 0.99991188

Convergence Angle: -00 45 41.40613

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 54.05427	117 38 08.75058	2200532.420	6140187.232	1305.211
2007.00	33 41 54.07092	117 38 08.76626	2200534.12	6140185.93	

References: A/NE-IRV, 1364-1389, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR EC 6-1974", IN OCS WELL MONUMENT DOWN 2.0'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 1.45 MILES NW'LY FROM ITS INTER WITH LIVE OAK CANYON RD. PER RSB 173/1-10.

