

GPS #: 2563

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/F-3

City / Location: Unin., Orange County

Scale Factor: 0.99997365

Ellipsoid Red. Factor: 0.99994462

Combination Factor: 0.99991827

Convergence Angle: -00 45 25.61358

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 32.73797	117 37 40.01165	2198345.765	6142586.655	1157.882
2007.00	33 41 32.75457	117 37 40.02737	2198347.46	6142585.35	

References: A/5-7, 6&8, 37-67, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR", IN OCS WELL MONUMENT DOWN 1.7'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 0.8 MILES NW'LY FROM ITS INTER WITH LIVE OAK CANYON RD., IN THE NORTH BOUND LN. PER RSB 173/1-10.

