

GPS #: 2570

Date Destroyed:

Date Revised: 9/16/2010

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/G-4

City / Location: Unin., Orange County

Scale Factor: 0.99997290

Ellipsoid Red. Factor: 0.99995201

Combination Factor: 0.99992491

Convergence Angle: -00 45 11.64034

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 07.64705	117 37 14.58345	2195781.464	6144701.663	1003.367
2007.00	33 41 07.66376	117 37 14.59890	2195783.17	6144700.38	

References: A/5-7, 6&8, 37-67, RSB 173/1-10

Description:

FD PUNCHED ALUMINUM DISK STAMPED "ORANGE COUNTY SURVEYOR PI 2 1974", IN OCS WELL MONUMENT DOWN 1.8'. LOCATED ALONG THE CENTERLINE OF SANTIAGO CANYON RD., 0.1 MILES NW'LY FROM ITS INTER WITH LIVE OAK CANYON RD., IN THE NORTH BOUND LN. PER RSB 173/1-10.

