

GPS #: 2590

Date Destroyed:
Date Revised: 6/8/1999
Benchmark Designation: 3EE-26-92
OCS Index Map: 6LB
Page/Grid: 922/G-4
City / Location: Unin., Orange County

Scale Factor: 0.99996365
Ellipsoid Red. Factor: 0.99997737
Combination Factor: 0.99994102
Convergence Angle: -00 45 30.62267

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 02.99140	117 37 49.12708	2158964.148	6141295.006	472.909
2007.00	33 35 03.00816	117 37 49.14278	2158965.86	6141293.70	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3EE-26-92" SET FLUSH AT THE SOUTH EAST CORNER OF A 4 FT. BY 5 FT. CATCH BASIN. MONUMENT IS LOCATED 5 FT. EASTERLY OF THE EASTERLY CURB FACE ALONG ANTONIO, IN THE NORTHEAST CORNER OF ANTONIO PARKWAY AND OSO PARKWAY, 44 FT. EASTERLY OF CENTERLINE OF ANTONIO PARKWAY, 200 FT. NORTHERLY OF CENTERLINE OF OSO PARKWAY. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

