

GPS #: **2593**

Date Destroyed:
Date Revised: 6/8/1999
Benchmark Designation: AP-03-99
OCS Index Map: 6LB
Page/Grid: 952/H-4
City / Location: Unin., Orange County

Scale Factor: 0.99996008
Ellipsoid Red. Factor: 0.99998616
Combination Factor: 0.99994625
Convergence Angle: -00 45 12.03258

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 54.38028	117 37 15.29725	2139863.757	6143906.076	289.137
2007.00	33 31 54.39724	117 37 15.31283	2139865.49	6143904.78	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-03-99" SET IN 6 IN. x 6 IN. CONCRETE POST. MONUMENT IS LOCATED FROM THE INTERSECTION OF ORTEGA HIGHWAY AND ANTONIO PARKWAY, PROCEED NORTHERLY 0.9 MILES ALONG ANTONIO PARKWAY (SOUTHERLY 3.85 MILES FROM OSO PARKWAY). SAID MONUMENT BEING 6' EASTERLY FROM EDGE OF PAVEMENT OF THE NORTHBOUND LANES, SET IN BETWEEN THE BEGINNING OF 2 CONCRETE "V" DRAIN DITCHES, WITNESSED BY 2 ORANGE CARSONITE WITNESS POSTS. MONUMENT IS SET UP 0.2 FT. ABOVE THE DIRT SURFACE.

