

**GPS #:** **2596**

**Date Destroyed:** **10/31/2000**  
**Date Revised:** **8/25/2005**  
**Benchmark Designation:** **AP-06-99**  
**OCS Index Map:** **6LB**  
**Page/Grid:** **952/G-1**  
**City / Location:** **Unin., Orange County**

**Scale Factor:** **0.99996138**  
**Ellipsoid Red. Factor:** **0.99997938**  
**Combination Factor:** **0.99994076**  
**Convergence Angle:** **-00 45 28.95785**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 08.43440	117 37 46.09748	2147382.643	6141398.093	431.000
2007.00	33 33 08.45120	117 37 46.11350	2147384.36	6141396.76	

**References:** OCS SURVEY FILE # 989GL9179

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: ORIGINALLY DESCRIBED BY OCS 2/25/99 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-06-99" SET IN 6" x 6" CONCRETE POST, UP 0.2' FROM DIRT SURFACE. TO REACH THE BENCHMARK FROM THE INTERSECTION OF OSO PARKWAY AND ANTONIO PARKWAY, PROCEED SOUTHERLY 2.3 MILES ALONG ANTONIO PARKWAY (NORTHERLY 2.45 MILES FROM ORTEGA HIGHWAY). SAID MONUMENT BEING 3' EASTERLY FROM TOP OF AC CURB OF THE NORTHBOUND LANES, 44' NORTHERLY FROM THE CENTER OF A CONCRETE "V" DITCH, WITNESSED BY 2 ORANGE CARSONITE WITNESS POSTS.

NO  
LOCATION  
MAP