

GPS #: 2597

Date Destroyed: 10/31/2000
Date Revised: 8/25/2005
Benchmark Designation: AP-07-99
OCS Index Map: 6LB
Page/Grid: 952/F-7
City / Location: Unin., Orange County

Scale Factor: 0.99996189
Ellipsoid Red. Factor: 0.99997728
Combination Factor: 0.99993917
Convergence Angle: -00 45 30.59816

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 35.51435	117 37 49.08248	2150122.911	6141181.730	474.737
2007.00	33 33 35.53128	117 37 49.09822	2150124.64	6141180.42	

References: OCS SURVEY FILE # 989GL9179

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: ORIGINALLY DESCRIBED BY OCS 2/25/99 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-07-99" SET IN 6" x 6" CONCRETE POST, UP 0.2' FROM DIRT SURFACE. TO REACH THE BENCHMARK FROM THE INTERSECTION OF OSO PARKWAY AND ANTONIO PARKWAY, PROCEED SOUTHERLY 1.7 MILES ALONG ANTONIO PARKWAY (NORTHERLY 3.0 MILES FROM ORTEGA HIGHWAY). SAID MONUMENT BEING 3' EASTERLY FROM TOP OF AC CURB OF THE NORTHBOUND LANES, 123' SOUTHERLY FROM THE CENTER OF A 4' WIDE AC DRAIN OUTLET, WITNESSED BY 2 ORANGE CARSONITE WITNESS POSTS.

NO
LOCATION
MAP