

GPS #: 2599

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation: AP-09-99

OCS Index Map: 6LB

Page/Grid: 922/F-5

City / Location: Unin., Orange County

Scale Factor: 0.99996306

Ellipsoid Red. Factor: 0.99997673

Combination Factor: 0.99993979

Convergence Angle: -00 45 35.22725

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 34.87443	117 37 57.50639	2156131.791	6140548.499	486.298
2007.00	33 34 34.89126	117 37 57.52226	2156133.51	6140547.18	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-09-99" SET IN THE SOUTHEASTERLY CORNER OF A CONCRETE BRIDGE DECK, FLUSH WITH CONCRETE SURFACE. TO REACH THE BENCHMARK FROM THE INTERSECTION OF OSO PARKWAY AND ANTONIO PARKWAY, PROCEED SOUTHERLY 0.5 MILES ALONG ANTONIO PARKWAY TO THE SOUTHEAST CORNER OF THE BRIDGE (WILDLIFE CROSSING). MONUMENT IS LOCATED 25 FT. NORTHERLY FROM THE SOUTHERLY EDGE OF THE DECK AND 2 FT. WESTERLY FROM A CONCRETE GUARDRAIL. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

