

GPS #: **2605**

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-5

City / Location: Unin., Orange County

Scale Factor: 0.99995968

Ellipsoid Red. Factor: 0.99999379

Combination Factor: 0.99995346

Convergence Angle: -00 45 08.42975

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 29.72764	117 37 08.74090	2137364.877	6144428.304	129.842
2007.00	33 31 29.74450	117 37 08.75657	2137366.60	6144427.00	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.9' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 0.4 MILES NORTHERLY FROM ITS INTERSECTION WITH ORTEGA HIGHWAY (4.3 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY), 53' WESTERLY OF THE EASTERLY A.C. BERM.

