

GPS #: 2607

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-4

City / Location: Unin., Orange County

Scale Factor: 0.99996006

Ellipsoid Red. Factor: 0.99998660

Combination Factor: 0.99994666

Convergence Angle: -00 45 11.72058

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 52.88901	117 37 14.72948	2139712.407	6143952.152	280.013
2007.00	33 31 52.90599	117 37 14.74513	2139714.14	6143950.85	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 0.85 MILES NORTHERLY FROM ITS INTERSECTION WITH ORTEGA HIGHWAY (3.85 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM

