

GPS #: 2608

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-4

City / Location: Unin., Orange County

Scale Factor: 0.99996017

Ellipsoid Red. Factor: 0.99998399

Combination Factor: 0.99994416

Convergence Angle: -00 45 15.76052

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 59.52396	117 37 22.08127	2140391.174	6143338.704	334.563
2007.00	33 31 59.54086	117 37 22.09682	2140392.90	6143337.41	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY 1.05 MILES NORTHERLY FROM ITS INTERSECTION WITH ORTEGA HIGHWAY (3.65 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM.

