

**GPS #:** 2610

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-3

City / Location: Unin., Orange County

Scale Factor: 0.99996029

Ellipsoid Red. Factor: 0.99998154

Combination Factor: 0.99994183

Convergence Angle: -00 45 18.73326

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 06.66841	117 37 27.49100	2141119.281	6142890.336	385.747
2007.00	33 32 06.68535	117 37 27.50658	2141121.01	6142889.04	

References: OCS SURVEY FILE # 989GL9179

**Description:**

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.2 MILES NORTHERLY FROM ITS INTERSECTION WITH ORTEGA HIGHWAY (3.5 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM.

