

GPS #: 2611

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/G-2

City / Location: Unin., Orange County

Scale Factor: 0.99996084

Ellipsoid Red. Factor: 0.99997599

Combination Factor: 0.99993683

Convergence Angle: -00 45 27.11999

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 38.46665	117 37 42.75299	2144350.117	6141641.066	501.705
2007.00	33 32 38.48353	117 37 42.76880	2144351.84	6141639.75	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.9 MILES NORTHERLY FROM ITS INTERSECTION WITH ORTEGA HIGHWAY (2.8 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY), 61' WESTERLY OF THE EASTERLY A.C. BERM.

