

**GPS #:** 2616

**Date Destroyed:** 10/27/2014  
**Date Revised:** 6/8/1999  
**Benchmark Designation:**  
**OCS Index Map:** 6LB  
**Page/Grid:** 952/G-1  
**City / Location:** Unin., Orange County

**Scale Factor:** 0.99996138  
**Ellipsoid Red. Factor:** 0.99997942  
**Combination Factor:** 0.99994080  
**Convergence Angle:** -00 45 29.34782

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 08.17649	117 37 46.80714	2147357.372	6141337.695	430.114
2007.00	33 33 08.19331	117 37 46.82319	2147359.09	6141336.36	

**References:** OCS SURVEY FILE # 989GL9179

**Description:**

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.6' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 2.25 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (2.45 MILES NORTHERLY OF ORTEGA HIGHWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM

