

**GPS #:** 2617

**Date Destroyed:** 9/4/2013  
**Date Revised:** 6/8/1999  
**Benchmark Designation:**  
**OCS Index Map:** 6LB  
**Page/Grid:** 952/G-7  
**City / Location:** Unin., Orange County

**Scale Factor:** 0.99996167  
**Ellipsoid Red. Factor:** 0.99997821  
**Combination Factor:** 0.99993989  
**Convergence Angle:** -00 45 31.42714

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 23.98616	117 37 50.59104	2148959.466	6141038.652	455.265
2007.00	33 33 24.00304	117 37 50.60670	2148961.19	6141037.35	

**References:** OCS SURVEY FILE # 989GL9179

**Description:**

GPS POSITION NO LONGER VALID. (SEE DATE IN DESTROYED BOX) - DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK DOWN 1.6' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.95 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (2.75 MILES NORTHERLY OF ORTEGA HIGHWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM

NO  
LOCATION  
MAP