

GPS #: 2619

Date Destroyed:

Date Revised: 10/10/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/G-7

City / Location: Unin., Orange County

Scale Factor: 0.99996188

Ellipsoid Red. Factor: 0.99997739

Combination Factor: 0.99993927

Convergence Angle: -00 45 31.16053

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 34.81461	117 37 50.10587	2150053.335	6141094.198	472.502
2007.00	33 33 34.83149	117 37 50.12160	2150055.06	6141092.89	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK STAMPED "ORANGE COUNTY SURVEYOR" DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.75 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (2.95 MILES NORTHERLY OF ORTEGA HIGHWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM.

