

**GPS #:** 2620

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-6

City / Location: Unin., Orange County

Scale Factor: 0.99996219

Ellipsoid Red. Factor: 0.99997613

Combination Factor: 0.99993832

Convergence Angle: -00 45 28.19814

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 50.95689	117 37 44.71499	2151678.773	6141571.931	498.729
2007.00	33 33 50.97380	117 37 44.73063	2151680.50	6141570.63	

References: OCS SURVEY FILE # 989GL9179

## Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK STAMPED DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.4 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (3.3 MILES NORTHERLY OF ORTEGA HIGHWAY), 61' WESTERLY OF THE EASTERLY A.C. BERM.

