

GPS #: **2622**

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-6

City / Location: Unin., Orange County

Scale Factor: 0.99996258

Ellipsoid Red. Factor: 0.99997461

Combination Factor: 0.99993719

Convergence Angle: -00 45 31.55110

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 11.02996	117 37 50.81662	2153714.362	6141082.534	530.694
2007.00	33 34 11.04678	117 37 50.83241	2153716.08	6141081.22	

References: OCS SURVEY FILE # 989GL9179

Description:

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK STAMPED DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 1.0 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (3.7 MILES NORTHERLY OF ORTEGA HIGHWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM.

