

**GPS #:** **2623**

Date Destroyed:

Date Revised: 6/8/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/F-5

City / Location: Unin., Orange County

Scale Factor: 0.99996264

Ellipsoid Red. Factor: 0.99997438

Combination Factor: 0.99993701

Convergence Angle: -00 45 33.36168

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 13.86780	117 37 54.11149	2154004.872	6140807.570	535.452
2007.00	33 34 13.88462	117 37 54.12723	2154006.59	6140806.26	

References: OCS SURVEY FILE # 989GL9179

**Description:**

DESCRIBED BY OCS 6/2/99 - FOUND 2" BRASS OCS DISK STAMPED DOWN 1.7' IN O.C.S. WELL MONUMENT, STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 0.9 MILES SOUTHERLY FROM ITS INTERSECTION WITH OSO PARKWAY (3.8 MILES NORTHERLY OF ORTEGA HIGHWAY), 60' WESTERLY OF THE EASTERLY A.C. BERM.

