

**GPS #:** 2630

Date Destroyed:

Date Revised: 6/9/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-4

City / Location: Unin., Orange County

Scale Factor: 0.99996360

Ellipsoid Red. Factor: 0.99992636

Combination Factor: 0.99988997

Convergence Angle: -00 45 31.28592

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 01.05019	117 37 50.33406	2158769.304	6141190.307	469.094
2007.00	33 35 01.06699	117 37 50.34990	2158771.02	6141188.99	

References: MM 720/13-15

**Description:**

DESCRIBED BY OCS 3/10/99 - FOUND 2" BRASS CAP STAMPED "LS 5557" DOWN 1.2' IN OCS WELL MONUMENT LOCATED AT THE CENTERLINE INTERSECTION OF ANTONIO PARKWAY AND OSO PARKWAY. (REPLACES GPS # 0198)

