

GPS #: 3008

Date Destroyed:

Date Revised: 5/22/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/C-4

City / Location: Garden Grove

Scale Factor: 0.99998553

Ellipsoid Red. Factor: 1.00000165

Combination Factor: 0.99998718

Convergence Angle: -00 56 37.48220

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 18.70321	117 58 02.66340	2234845.166	6039867.097	-34.573
2007.00	33 47 18.71932	117 58 02.68038	2234846.82	6039865.69	

References: GARDEN GROVE TIE BOOK 1 PAGE43, RSB 149/21-36, CR 2003-0950, CR2005-1615, CR2006-1015, CR 2008-1753

Description:

FD PUNCHED HEX BOLT, DOWN 0.8' IN WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF CHAPMAN AVE., 5.00' E'LY FROM ITS CENTERLINE INTER WITH GILBERT ST.

