

GPS #: 3013R2

Date Destroyed:

Date Revised: 10/20/2013

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/D-4

City / Location: Garden Grove

Scale Factor: 0.99998554

Ellipsoid Red. Factor: 1.00000129

Combination Factor: 0.99998684

Convergence Angle: -00 56 20.30208

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 18.91848	117 57 31.39937	2234823.572	6042505.812	
2007.00	33 47 18.93464	117 57 31.41643	2234825.23	6042504.40	

References: RSB 149/21-36, CR 2001-0050, CR 2005-1614, CR 2006-1014, CR 2013-2129

Description:

FD NAIL AND TAG STAMPED "LS 5822" IN LIEU OF PK NAIL AND WASHER STAMPED "LS 5411" IN LIEU OF PUNCHED BOLT, DOWN 1.1' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2006-101. STATION IS LOCATED IN THE INTERSECTION OF BROOKHURST ST. AND CHAPMAN AVE.

