

GPS #: 3020

Date Destroyed:

Date Revised: 5/13/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/D-4

City / Location: Anaheim

Scale Factor: 0.99999301

Ellipsoid Red. Factor: 1.00000024

Combination Factor: 0.99999325

Convergence Angle: -00 56 20.93880

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 23.15829	117 57 32.55809	2253446.399	6042713.282	-5.023
2007.00	33 50 23.17458	117 57 32.57598	2253448.07	6042711.80	

References: RSB 35/20, RSB 149/21-36, CR 2002-691, CR 2008-0624

Description:

FD HEX BAR IN CONC., DOWN 2.3' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF EAST CRESCENT AVE. AND BROOKHURST ST.

