

GPS #: 3022R1

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/E-3

City / Location: Anaheim

Scale Factor: 0.99999413

Ellipsoid Red. Factor: 0.99999956

Combination Factor: 0.99999369

Convergence Angle: -00 56 06.52532

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 49.23290	117 57 06.32872	2256045.616	6044968.484	
2007.00	33 50 49.24903	117 57 06.34642	2256047.27	6044967.02	

References: RSB 149/21-36, CR 2001-0685

Description:

FD GEAR SPIKE AND "CITY OF ANAHEIM SURVEY DIVISION" WASHER FLUSH, IN LIEU OF SPIKE. MONUMENT WAS RESET PER CORNER RECORD # 2001-685. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF LA PALMA AVE. AND ROMNEYA DR.

