

GPS #: 3042R2

Date Destroyed:

Date Revised: 4/11/2016

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/F-3

City / Location: Anaheim

Scale Factor: 0.99999415

Ellipsoid Red. Factor: 0.99999909

Combination Factor: 0.99999323

Convergence Angle: -00 55 46.56545

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 49.51375	117 56 30.00619	2256024.149	6048032.139	
2007.00	33 50 49.52994	117 56 30.02382	2256025.81	6048030.68	

References: RSB 149/21-36, CR 2002-0511, CR 2002-0684, CR 2007-2496

Description:

FOUND 3042R2 SPIKE AND CITY OF ANAHEIM TAG FLUSH PER CR 2007-2496 IN LIEU OF, FOUND PK NAIL WITH "C OF A" TAG PER 2002-0684 IN LIEU OF FOUND PUNCHED SPIKE AND "C OF A" TAG PER CORNER RECORD # 2002-0511, ORIGINAL MONUMENT BEING PUNCHED HEX BOLT, DOWN 1.2' IN WELL MONUMENT PER MONUMENT RECORD # 3042. STATION IS LOCATED AT CENTERLINE INTER OF LA PALMA AVE. AND EUCLID ST.

