

GPS #: 3045R2

Date Destroyed:

Date Revised: 4/24/2012

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 768/H-4

City / Location: Anaheim

Scale Factor: 0.99999266

Ellipsoid Red. Factor: 0.99999839

Combination Factor: 0.99999105

Convergence Angle: -00 55 14.98886

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 14.86313	117 55 32.54384	2252443.684	6052821.838	
2007.00	33 50 14.87949	117 55 32.56131	2252445.36	6052820.39	

References: RSB 149/21-36, CR 2001-0682, CR 2011-3114, cr 2012-0100

Description:

FD PUNCH SPIKE AND WASHER STAMPED "LS 6871" FLUSH PER CR 2012-0100 IN LIEU OF PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "3045R1 3-01" FLUSH, ORIGINAL MONUMENT BEING PK NAIL AND BRASS WASHER, STAMPED "LS 397". MONUMENT WAS RESET PER CORNER RECORD # 2001-0682. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF SYCAMORE ST. AND OHIO ST.

