

GPS #: 3062

Date Destroyed:

Date Revised: 6/18/2013

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 768/H-7

City / Location: Anaheim

Scale Factor: 0.99998974

Ellipsoid Red. Factor: 0.99999904

Combination Factor: 0.99998878

Convergence Angle: -00 55 11.76546

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 05.01982	117 55 26.67794	2245376.562	6053203.231	20.085
2007.00	33 49 05.03608	117 55 26.69535	2245378.23	6053201.79	

References: RSB 100/24, RSB 149/10-20, CR 2000-0505, CR 2013-0215

Description:

FD PUNCHED BRASS CAP IN CONC., DOWN 1.1' IN CITY OF ANAHEIM WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF BALL RD. AND WEST ST.

