

GPS #: 3070R1

Date Destroyed: 7/25/2000

Date Revised: 6/8/2000

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 798/J-1

City / Location: Anaheim

Scale Factor: 0.99998895

Ellipsoid Red. Factor: 0.99999880

Combination Factor: 0.99998775

Convergence Angle: -00 54 54.49336

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 45.38427	117 54 55.24658	2243349.506	6055823.131	
2007.00	33 48 45.40050	117 54 55.26385	2243351.17	6055821.70	

References: PMB 191/22-23, RSB 149/10-20, CR 2000-0097

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PK NAIL WITH CITY OF ANAHEIM TAG ON SURFACE IN LIEU OF ORIGINAL MONUMENT BEING A PUNCHED 2" BRASS CAP IN CONC., DOWN 1.5' IN WELL MONUMENT. STATION IS LOCATED AT THE INTER OF THE CENTERLINE OF MANCHESTER AVE. AND THE APPARENT CENTERLINE OF HARBOR BLVD. MONUMENT RESET PER CORNER RECORD # 2000-97.