

GPS #: 3075R1

Date Destroyed:

Date Revised: 5/6/2004

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 798/J-6

City / Location: Garden Grove

Scale Factor: 0.99998361

Ellipsoid Red. Factor: 1.00000045

Combination Factor: 0.99998406

Convergence Angle: -00 54 53.42859

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 27.82966	117 54 53.30894	2229444.166	6055764.601	
2007.00	33 46 27.84590	117 54 53.32583	2229445.83	6055763.20	

References: GARDEN GROVE TIE BOOK 2 PAGE 145A, RSB 149/10-20, CR 2003-0933

Description:

FD PUNCHED 2 1/2" BRASS CAP, DOWN 1.2' IN WELL MONUMENT IN LIEU OF 3/8" BAR IN CONC., DOWN 1.2' IN WELL MONUMENT. MONUMENT WAS SET PER CORNER RECORD 2003-0933. STATION IS LOCATED AT CENTERLINE INTER OF PALM ST. AND GARDEN GROVE BLVD.

