

**GPS #:** 3081R2

Date Destroyed:

Date Revised: 5/13/2014

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/A-1

City / Location: Anaheim

Scale Factor: 0.99998865

Ellipsoid Red. Factor: 0.99999844

Combination Factor: 0.99998709

Convergence Angle: -00 54 36.13063

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 38.15511	117 54 21.83049	2242573.940	6058630.740	
2007.00	33 48 38.17132	117 54 21.84774	2242575.60	6058629.31	

References: RSB 149/10-20, CR 2001-0352, CR 2013-2402, CR 2014-0138

**Description:**

FD 2" PUNCHED ALUMINUM DISK STAMPED "ANAHEIM SURVEY PLS 6871", DOWN 1.1' IN WELL PER CR 2014-0138 IN LIEU OF PUNCHED SPIKE AND BRASS OCS WASHER STAMPED "3081R1 01-01" ORIGINAL MONUMENT BEING CONC. NAIL AND 3/4" BRASS TAG. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-0352. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF CERRITOS AVE. AND ANAHEIM BLVD.

