

GPS #: **3093R1**

Date Destroyed:

Date Revised: 5/8/2003

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/C-3

City / Location: Anaheim

Scale Factor: 0.99998659

Ellipsoid Red. Factor: 0.99999849

Combination Factor: 0.99998508

Convergence Angle: -00 53 55.90856

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 46.08762	117 53 08.63523	2237213.915	6064723.592	
2007.00	33 47 46.10367	117 53 08.65204	2237215.56	6064722.20	

References: RSB 149/10-20, CR 2002-0683

Description:

FD PK NAIL AND "C OF A" TAG IN LIEU OF SPIKE. MONUMENT WAS RESET PER CORNER RECORD # 2002-0683B. STATION IS LOCATED AT THE MOST W'LY APPARENT CENTERLINE INTER OF ORANGEWOOD AVE. AND DUPONT DR.

