

GPS #: 3102

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/D-3

City / Location: Anaheim

Scale Factor: 0.99998656

Ellipsoid Red. Factor: 0.99999844

Combination Factor: 0.99998501

Convergence Angle: -00 53 48.29536

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 45.43113	117 52 54.78092	2237129.243	6065891.628	32.579
2007.00	33 47 45.44731	117 52 54.79766	2237130.90	6065890.24	

References: ANAHEIM TIE BOOK 47 PAGE 217, RSB 149/10-20

Description:

FD 2" BRASS CAP, DOWN 1.7' IN CITY OF ANAHEIM WELL MONUMENT. STATION IS LOCATED AT THE POINT OF REVERSE CURVE ALONG THE CENTERLINE OF ORANGEWOOD, 23.24' E'LY, AS MEASURED ALONG THE CENTERLINE, FROM ITS CENTERLINE INTER WITH RAMPART ST.

